


[Bidder's Letterhead]

[Date]

To: Tarlac State University
 Re: [Invitation to Bid No.]

BILL OF QUANTITIES

Item No. (1)	Work Description (2)	Materials, supplies, etc.		Work Item		Direct Cost	Indirect Cost	Total Direct & Indirect Cost (9)	Value Added Tax (10)	Total Cost (11)
		Quantity (3)	Unit (4)	Quantity (5)	Unit (6)	Materials, Labor, & Equipment (7)	Overhead, Contingencies, Miscellaneous, & Profit (8)			
1 General Requirements										
1.1	Mobilization & Demobilization			1	lot					
1.2	Construction Occupational Safety & Health			1	lot					
1.3	Temporary Facilities and Barricade			1	lot					
1.4	Project Billboard			1	lot					
1.5	Permit and Clearances			1	lot					
									Sub-Total	
2 Demolition, Hauling, Disposal and Restoration										
2.1	Demolition/Removal/Dismantling of Existing Concrete Parapet, Extended Concrete Columns, Concrete Slab, Concrete Ramp and all other affected areas			1	lot					
2.2	Clearing, Hauling and Disposal of Debris and Scrap Materials			1	lot					
2.3	Restoration of all affected areas			1	lot					
									Sub-Total	
3 Structural Works										
3.1	3000 psi Concrete Footing including Grade 40 reinforcement, Scaffolding and Formworks			1	lot					
3.2	3000 psi Concrete Pedestal Column including Grade 40 reinforcement, Scaffolding and Formworks			1	lot					
3.3	3000 psi Concrete Grade Beam including Grade 40 reinforcement, Scaffolding and Formworks			1	lot					
3.4	A36 Structural Steel Column and Connections including Scaffolding			1	lot					
3.5	A36 Structural Steel Beam, Lintel Beam and Connections including Scaffolding			1	lot					
3.6	Roof Framing System			1	lot					
									Sub-Total	



4 Architectural Works								
4.1 Roofing Works								
4.1.1	Roofing Materials - 0.5mm thk. Pre-painted Roof sheets, Flashings, Gutters, and 10mm thk. Aluminium Film Laminated Foam Two Sides w/ 12.5mm Welded Wire #21 including consumables (sealant, tekscrew, rivet etc.)		1	lot				
4.1.2	Canopy - 3.00 mm thk. Solid Polycarbonate Sheet on Steel Framing System		1	lot				
4.1.3	Parapet - 4.00 mm thk. Aluminum Composite Panel with Sub-frame on Steel Main Framing System		1	lot				
								Sub-Total
4.2 Masonry Works								
4.2.1	4" CHB Walls (including tie wire, mortar and 10mm Ø steel reinforcement every three layer of CHB layer and 0.60m vertical spacing)		1	lot				
4.2.2	Cement Plastering of Walls, Pedestal Columns, Lintel Beams, Window & Door Openings etc.		1	lot				
								Sub-Total
4.3 Ceiling Works								
4.3.1	9.00 mm thk. Gypsum Board Ceiling on Metal Furring Framing System with complete accessories		1	lot				
4.3.2	0.50 mm thk. Pre-painted Spandrel including steel framing and mouldings		1	lot				
								Sub-Total
4.4 Steel Works								
4.4.1	Steel Stairway System		1	lot				
4.4.2	Steel Railing System		1	lot				
								Sub-Total
4.5 Painting								
4.5.1	Semi-Gloss Latex Painting and Re-painting on Walls, Columns, Beams, Window & Door Opening, Downspout (including scraping of old paint for re-painting, surface preparation, neutralizer, primer and top coats)		1	lot				
4.5.2	Quick Drying Enamel Paint for Painting and Re-painting of Steel (including surface preparation, primer and top coats)		1	lot				
4.5.3	Flat Latex Painting and Re-painting on Ceiling (including surface preparation, primer and top coats)		1	lot				
4.5.4	Metal Primer Paint Finish on Roof Framing (including surface preparation)		1	lot				
4.5.5	Concrete Epoxy Paint on Concrete Floor Finish (including surface preparation, primer and top coats)		1	lot				
								Sub-Total

4.6	Tiles and Baseboard								
4.6.1	150mm X 900mm X 3mm thk. Vinyl Floor Tiles on minimum 25mm thk. Levelled Concrete Topping with 2" x 2" x 1.5mm thk. Steel Matting Reinforcement including consumables (adhesive, G.I. Wire etc.)		1	lot					
4.6.2	1" x 4" PVC Baseboard System		1	lot					
									Sub-Total
4.7	Dry Wall Partition and False Column								
4.7.1	Dry Wall - 4.5mm thk. Fiber Cement Board on Metal Framing including consumables (blind rivet, black screw, concrete nail etc.)		1	lot					
4.7.2	False Column - 4.5mm thk. Fiber Cement Board on Steel Framing including consumables (blind rivet, black screw, concrete nail etc.)		1	lot					
									Sub-Total
4.8	Doors								
4.8.1	2.10m x 0.80m x 12mm thk. Tempered glass with frosted decals single panel swing glass door w/ closer and fd100 top & bottom frame with s304 stainless h-type door handle and complete accessories		3	set					
4.8.2	2.10m x 1.60m Analok aluminum frame sliding doors with 6mm thk. Clear tempered glass with frosted tint and complete accessories		3	set					
4.8.3	2.40m x 3.60m Analok aluminum frame sliding and fixed door with 6mm thk. Clear tempered glass with frosted tint and complete accessories		2	set					
									Sub-Total
4.9	Windows								
4.9.1	1.20m x 1.80m Analok (1 3/4" x 4") aluminum awning window w/ 6mm thk. One way reflective (interior) tempered bronze glass		7	set					
4.9.2	1.20m x 0.60m Analok (1 3/4" x 4") aluminum awning window w/ 6mm thk. One way reflective (interior) tempered bronze glass		3	set					
									Sub-Total
4.10	Land Development								
4.10.1	Embankment with Compaction		1	lot					
4.10.2	Perimeter Embankment Wall including wall footing and perimeter beam		1	lot					
4.10.3	Perimeter Embankment Wall including wall footing and perimeter beam		1	lot					
									Sub-Total
4.11	Furnishing and Installation								
4.11.1	TARLAC STATE UNIVERSITY Signage - Stainless Steel Guage #18, 2" Build Up Sidings and Stainless Pin Mounted including Complete accessories		2	set					
									Sub-Total
5	Plumbing Works								
5.1	Storm Drain System								
5.1.1	3" x 4" Rectangular PVC Downspout including fittings		1	lot					
5.1.2	0.5m x 0.5m Concrete Catch Basin with Steel Grating Cover		5	set					
5.1.3	4" PVC Drainage Pipe S1000 Series		1	lot					
5.1.4	ACU Condensate Drain Pipes		1	lot					
									Sub-Total

6 Electrical Works									
6.1	Lighting System		1	lot					
6.2	Power System		1	lot					
6.3	Auxillary System		1	lot					
		Total Bid Price		<i>(State total amount of Bid in words)</i>				<i>(Total amount in figures)</i>	

[Signature]
 [Name of Authorized Signatory]
 [Position/Title of Authorized Signatory]

